ROYALTY CALCULATION

Name of work; Improvements to drain all round the park in ward no;14 Dasarahalli zone

Description	Qty in Cum	Constant	Total Qty	
Plain Cement Concrete 1:4;8				
Sand	283.43	0.465	131.79	
Jelly	283.43	0.892	252.82	
Cement Concrete M20				
Sand	455.51	0.43	195.87	
Jelly	455.51	0.69	314.30	
Precast Concrete Slab 100MM thick				
Sand	100.88	0.46	46.40	
Jelly	100.88	0.88	88.77	
Precast Concrete Slab 250 MM thick				
Sand	33.75	0.43	14.51	
Jelly	33.75	0.69	23.29	
Precast Concrete Kerb				
Sand	62.57	0.43	26.91	
Jelly	62.57	0.69	43.17	
	ABSTRACT			
Sl	Items	Qty	Rate	Amount
1	Sand	400.97	138	55333.86
2	Jelly	633.58	126	79831.08
			Total	1,35,164.94

Asst.Engineer 02/08/23
Project Division

Asst.Executive Engineer 02/08/2023
Project Division

Asst. Executive Engineer
Project Division, Dasrahalli Zone
BBMP, Bangalore

Scanned with OKEN Scanner